

"ഭരണഭാഷ - മാതൃഭാഷ"

No.KSCSC/3205/2023/D32A(ECP)

തീയതി. 01-11-2024

നോട്ടീസ്

സപ്ലൈകോ, ഈസ് ലാന്റ് എൻക്ലേവ്, എളംകുളം ക്വാർട്ടർ നം. 104 ന്റെ മെയിന്റനൻസ് വർക്കുകൾ നിർവ്വഹിക്കുന്നതിനായി എംപാനൽ ഗവ.അംഗീകൃത കോൺട്രാക്ടർമാരിൽ നിന്നും, പ്രവർത്തി പരിചയമുള്ളവരിൽ നിന്നും ക്വട്ടേഷൻ ക്ഷണിക്കുന്നു.

Name of Work :- Maintenance works at Easland Enclave, Elamkulam,Quarter No.104.

Estimate :- Rs. 1,45,000/-(Excluding GST)

വിശദ വിവരങ്ങൾ എസ്റ്റേറ്റ്/ എഞ്ചിനീയറിംഗ് വിഭാഗങ്ങളിൽ ലഭ്യമാണ്. ക്വട്ടേഷൻ സമർപ്പിക്കേണ്ട അവസാന തീയതി. ~~23.11~~ 23.10.2024 , 11 AM. 5 pm

Ob
23/10/24
മാനേജർ (ഇ&സിപി)

Signed by
Rajeshkrishnan Gopalakrishnan
Date: 01-11-2024 15:24:03

F 255476/2024

QUOTATION OF EASLAND ENCLAVE FLAT NO:104-LABOUR-ESTIMATE AMOUNT:Rs.73,935/- (SEVENTY THREE THOUSAND NINE HUNDRED AND THIRTY FIVE)							
B	LABOUR						
Sl No	Description	Unit	Quantity	Rate	Amount	Remark	
B	LABOUR						
1	DISMANTLING WOODEN	Nos	1				
2	REMOVING WHITE OR COLOUR WASH	Sqft	3550				
3	EMULSION-PRIMER-INSIDE & OUTSIDE	Sqft	3270				
4	EMULSION INSIDE & OUTSIDE	Sqft	3270				
5	ENAMEL PAINTING-	Sqft	360				
6	VARNISHING	Sqft	810				
7	POLISHING WORK	Nos	2				
8	PLASTERING WORK	Nos	4				
9	WATER PROOF WORK	Nos	4				
10	TILE REMOVING & LAYING CHARGE	Nos	3				
11	TILE WORK CLEANING	Nos	1				
12	DISMANTLING ALUMINIUM PARTITIONS & REPAIR	Nos	5				
13	PLUMBERS	Nos	4				
14	CARPENTORS	Nos	5				
15	ACID WASH	Sqft	1200				
16	CLEANING WORKS	Nos	5				
	TOTAL AMOUNT-LABOUR				Rs:		

QUOTATION OF EASLAND ENCLAVE FLAT NO:104-MATERIALS-ESTIMATE AMOUNT:Rs.71.370/- (SEVENTY ONE THOUSAND THREE HUNDRED & SEVENTY ONLY)

A	PAINTING-MATERIALS					
SI No	Description	Unit	Quantity	Rate	Amount	Remark
1	EMULSION-PRIMER -INSIDE & OUTSIDE	Litre	33			
2	EMULSION INSIDE & OUTSIDE	Litre	28			
3	ENAMEL PAINTING	Litre	5			
4	VARNISH	Litre	8			
5	POLISHING	Litre	2			
6	PLASTERING MATERIALS	Sqm	24			
7	WATER PROOF TREATMENT	Sqft	200			
8	VETRIFIED TILE OF SIZE 600 X 600 mm	Sqft	32			
9	MATERIAL FOR TILE FIXING	Sqft	32			
10	CERAMIC TILE & MATERIAL	Sqft	11			
11	CP HEALTH FAUCET	Nos	1			
12	SS GRATINGS	Nos	1			

QUOTATION OF EASLAND ENCLAVE FLAT NO:104-MATERIALS-ESTIMATE AMOUNT:Rs.71.370/- (SEVENTY ONE THOUSAND THREE HUNDRED & SEVENTY ONLY)

A	PAINTING-MATERIALS					
SI No	Description	Unit	Quantity	Rate	Amount	Remark
13	WHITE CHINA PEDESTRAL TYPE WATER VITREOUS CHINA PEDESTAL TYPE WATER VCLOSET (EUROPEAN TYPE W.C PAN WITH SEAT & LID,10 LITRE LOW LEVEL WHITE P.V.C FLUSHING CISTERN ,INCLUDING FLUSH PIPE,WITH MANUALLY CONTROLLED DEVICE(HANDLE LEVER),CONFORMING TO IS :7231,WITH BALL FITTINGS & FIXTURES COMPLETE ,INCLUDING CUTTING & MAKING GOOD THE WALLS & FLOORS WHERE EVER REQUIRED W.C PAN WITH ISI MARKLED BLACK SOLOD PLASTIC SEAT & LIDCLOSET WITH SEAT & LID	Nos	1			
14	UPVC DOOR FRAME - TOLERANCE + OR - 1 MM WITH OVERALL WALL THICKNESS 2.0 MM	Nos	1			
15	UPVC DOOR SHUTTER	Sqft	35			
16	CP BRASS PILLAR TAP	Nos	1			
17	CP BRASS ANGLE VALVE FOR BASIN MIXER & GEYSER POINTS OF APPROVED QUALITY CONFORMING TO IS :893115 MM NOMINAL BORE	Nos	4			

QUOTATION OF EASLAND ENCLAVE FLAT NO:104-MATERIALS-ESTIMATE AMOUNT:Rs.71.370/- (SEVENTY ONE THOUSAND THREE HUNDRED & SEVENTY ONLY)

PAINING-MATERIALS						
SI No	Description	Unit	Quantity	Rate	Amount	Remark
A	MATERIALS					
18	BRASS STOP COCK	Nos	4			
19	PVC CONNECTION PIPE	Nos	5			
20	BRASS BIB COCK	Nos	4			
21	GLASS OF 4 MM THICKNESS	Sqft	7			
22	ALUMINIUM TEE CHANNELS	M	10			
23	ALUMINIUM TOWER BOLT-250 x 10 MM	Nos	4			
24	ALUMINIUM TOWER BOLT-200 x 10 MM	Nos	4			
25	MORTICE LATCH-CHROMIUM PLATED 100 MM WITH 6 LEVERS & A PAIR OF LEVER HANDLES OF APPROVED QUALITY WITH NECESSARY SCREWS	Nos	1			
26	ALUMINIUM ALDROP-200 MM	Nos	1			
27	ALUMINIUM ALDROP-300 MM	Nos	1			
28	PROVIDING & FIXING FLY PROOF WIRE GAUZE TO WINDOWS,CLERESTORY WINDOWS & DOORS WITH M.S FLAT 15 X 3 MM & NUTS & BOLTS COMPLETE .STAINLESS STEEL (GRADE 304) WIRE GAUZE OF 0.5 MM DIA WIRE & 1.4 MM APERTURE ON BOTH SIDES	Sqft	65			
29	BRASS TOWER BOLT-250 X 10 MM	Nos	5			
30	BRIGHT FINISHED BRASS HANGING TYPE FLOOR DOOR STOPPER WITH NECESSARY SCREWS	Nos	7			
31	TOWER BOLT-250 X 10 MM - BRASS WITH NECESSARY SCREWS	Nos	3			
TOTAL AMOUNT -MATERIALS					Rs:	