

**SUPPLYCO**

ESSENTIAL REQUIREMENTS TO THE REACH OF EVERYONE

**The Kerala State Civil Supplies Corporation Limited**  
(A fully owned Government of Kerala undertaking)

P.B. No.: 2030  
Maveli Bhavan,  
Maveli Road,  
Gandhi Nagar,  
Kochi-682 020  
GSTIN : 32AAACK6767FHZ5  
CIN : U52209KL1974SGC002615

ഭരണഭാഷ - മാതൃഭാഷKSCSC/2766/2023-D33(ECP)തീയതി . **21-11-2024**നോട്ടീസ്

സപ്ലൈകോ, കൊച്ചി ഡിപ്പോ ചുളിക്കൽഗോഡൗണിലെ ഇലക്ട്രിക്കൽ വർക്കുകൾ നിർവ്വഹിക്കുന്നതിനായി ഗവ.അംഗീകൃത കോൺട്രാക്ടർമാരിൽ നിന്നും, പ്രവർത്തി പരിചയമുള്ളവരിൽ നിന്നും ടെണ്ടറുകൾ ക്ഷണിക്കുന്നു.

Name of Work :-Electrical works at Chullickal Godown at Supplyco Kochi

Depot.

Estimate ; - Rs.1,45,410/- (Excluding GST)

വിശദ വിവരങ്ങൾ എസ്റ്റേറ്റ് എഞ്ചിനീയറിംഗ്

വിഭാഗങ്ങളിൽ ലഭ്യമാണ്. ടെണ്ടർ സമർപ്പിക്കേണ്ട

അവസാന തീയതി 30 .11.2024 , 5 P M

Signed by മാനേജർ (ഇ&സിപി)

Rajeshkrishnan Gopalakrishnan

Date: 21-11-2024 13:06:04

TENDER FORMAT OF ELECTRICAL WORKS AT CHULLIKKAL GODOWN						
TOTAL ESTIMATE AMOUNT:Rs 1,45,410/-						
SI No	Description	Unit	Quantity	Rate	Amount	Remark
<b>MATERIAL &amp; LABOUR</b>						
1	Supply & wiring points using rigid PVC conduit of 20mm size with saddles and 1 sq.mm PVC insulated stranded single core copper cable 650V grade and 1 sq.mm copper earth wire complete in suitable modular type metal box, 6A SP modular switches.					
a	6A light point	Nos	19			
b	Motor point included box and switch	Nos	1			
2	Combined plug point with 6A 3 pin plug socket controlled by 6A switch in the same switch board as that of light points.	Nos	10			
3	Supply & drawing the following sizes 650/1100V grade PVC insulated single core copper conductor cable in existing PVC conduits including necessary connections as required.					
a	1.5 sq.mm	m	30			
4	Supply & fixing the following size of PVC conduit with all accessories on surface.					
a	20 mm dia medium guage	m	30			
5	Supply, installation, terminations, testing & commissioning of 16 way double door DB comprising of					
a	6/10/16/25A SP MCB - 8 nos & 40 A SP 30 Ma ELCB-1 Nos	Nos	2			
6	Earthing works					
a	Supply of 10 SWG copper wire for earthing	m	120			

<b>TENDER FORMAT OF ELECTRICAL WORKS AT CHULLIKKAL GODOWN</b>						
<b>TOTAL ESTIMATE AMOUNT:Rs 1,45,410/-</b>						
<b>SI No</b>	<b>Description</b>	<b>Unit</b>	<b>Quantity</b>	<b>Rate</b>	<b>Amount</b>	<b>Remark</b>
	<b>MATERIAL &amp; LABOUR</b>					
b	Supply of 38mm GI pipe earthing, earthing compound, excavation, etc. as reqd.	Nos	2			
7	Supply and fixing 40A SP ELCB	Nos	2			
8	Supply and fixing 40W LED Bulb	Nos	30			
9	Supply and fixing 20W LED tub	Nos	10			
10	Supply and fixing terminal box included Wire and 40A isolator	Nos	1			
11	Additional maintenance work for damage switch replacing,box replacing and sockets replacing	Nos	1			
	<b>TOTAL</b>				<b>Rs:</b>	